Bruhath Bangalore Mahanagara Palike
Dasarahalli Zone
Schedule -B

Name of Work: Construction of Bengalore-One Office and tax Office, ward office and Multipurpose Building in Ward No.12, in Shettyhalli Sub Division.

Description of Work	Unit	Quantity as per Estimate	Quoted Rate	
			In Figures	In Words
Earthwork in surface excavation for levelling and loweringthe ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled including breaking of clods and neatly dressed as per specifications,	Cum	227.50	183.12	Rupees One Hundred Eighty Three And Paise Twelve Only
Earth work excavation for foundation of building water sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of colds complete as per specifications.	Cum	483.60	484.92	Rupees Four Hundred Eighty Four And Paise Ninety Two Only
Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift, complete as per specifications, specification.	Cum	33.89	2283.98	Rupees Two Thousand Two Hundred Eighty Three And Paise Ninety Eight On

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

	Providing and injecting chemical emulsion for chemical barrier underand around the column ..., walls, trenches,basement excavation, top surface of the plinth filling, junction of wall and floor, along the external perimeter of building, expansion joints, over the top surface of consolidated earth on which apron is to be laid, surrounding of pipes and conduits, with chloropyriphos emulsifiable concentrates of 20% concentration, including cost of chemical, diluting in water to one percent concentration, labour, HOM of equipments, complete as per specifications. (Plinth area of the building at ground floor only shall be measured)	Sqm	526.45	111.24	Rupees One Hundred Eleven And Paise Twenty Four Only
5	Providing and laying in position plain **cement concrete of mix 1:3:6 with OPC** cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	125.32	5609.52	Rupees Five Thousand Six Hundred Nine And Paise Fifty Two Only
6	Providing and constructing **granite /trap/ baslat size stone masonry in foundation** with cement mortar 1:6, stones hammerd dressed in courses not less than 20cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications	Cum	136.96	4853.52	Rupees Four Thousand Eight Hundred Fifty Three And Paise Fifty Two Only
7	Providing and constructing **granite /trap/ baslat size stone masonry in basement** with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications	Cum	46.53	5921.64	Rupees Five Thousand Nine Hundred Twenty One And Paise Sixty Four Only
8	**Providing ruled pointing to coursed stone masonry** with cement mortar 1:3 20mm deep, after raking joints to depth of 20mm necely lining, including cost of materials, labour, curing complete as per specifications	Sqm	39.78	153.36	Rupees One Hundred Fifty Three And Paise Thirty Six Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

	roviding and laying in position **plain cement concrete of nominal mix 1:2:4** using 20mm d down size graded granite metal machine mixed concrete liad in layers not exceeding 15cms thick well compacted in foundation plinth and cills including cost of all materials, labour HOM of machinery, curing complete as per specifications	Cum	21.84	5855.76	Rupees Five Thousand Eight Hundred Fifty Five And Paise Seventy Six Only
10	**Filling avaialble excavated earth** (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms in depth compacting each deposited layers by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specification	Cum	711.10	217.08	Rupees Two Hundred Seventeen And Paise Eight Only
11	Providing and laying in position reinforced cement concrete of **design mix M25 with OPC cement @ 340kgs**, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintles and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, ,pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications.	Cum	315.25	6528.60	Rupees Six Thousand Five Hundred Twenty Eight And Paise Sixty Only
12	**Providing and laying in position reinforced cement concrete of design mix M20** with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.05175cum and fine aggregtes @ 0.0345cum, with superplastisiser @0.225lts, machine mixed, well compacted for **plain chajja of 7.5 cms. average thickness**, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete but excluding cost of reinforcement as per specifications.	Cum	34.56	475.20	Rupees Four Hundred Seventy Five And Paise Twenty Only

EXECUTIVE ENGINEER-4

	roviding and fabricating TMT Steel (cold, wisted) reinforcement for R.C.C. work luding straightening, cutting, bending, ooking,placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design(laps and wasteage shall not measured and paid) cost of materials. labour. HOM of machinery complete as per specifications **Fe** 550	Ton	39.41	77239.44	Rupees Seventy Seven Thousand Two Hundred Thirty Nine And Paise Forty Four Only
14	**Providing and removing centering shuttering** strutting propping etc., and removal of form work for **columns,** pillars, abutments, post and struts square/ rectangular/ polygon in plan including cost of all materials labour complete as per specification	Sqm	315.90	492.48	Rupees Four Hundred Ninety Two And Paise Forty Eight Only
5	**Providing and removing centering shuttering** strutting propping etc., and removal of form work for sides and soffits of **beams beam houchings** cantilever girders bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specification	Sqm	344.73	315.36	Rupees Three Hundred Fifteen And Paise Thirty Six Only
	Providing and removing centering shuttering strutting propping etc., for **chejjas** corbels etc., including edges including cost of all materials, labour complete as per specifications	Sqm	8.16	348.84	Rupees Three Hundred Forty Eight And Paise Eighty Four Only
	Providing and removing centering, shuttering, strutting propping etc., and removal of form work for **stairs** (excluding landing) except spiral staircase including cost of all materials labour complete as per specification	Sqm	28.68	561.60	Rupees Five Hundred Sixty One And Paise Sixty Only
	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, **roofs,**landing, balconies and ikes thickness upto 200mm including cost of naterials, labour complete as per specification	Sqm	429.37	432.00	Rupees Four Hundred Thirty Two Only

EXECUTIVE ENGINEER-4

	oviding and constructing **pre cast concrete olid blocks** with compressive strength not less n 35 kg/sqm with cement mortar 1:4 asonry (quoins, jamb,closer blocks) with olid concrete blocks of size 400x200x200cms conforming to I.S: 2185/1965 in superstructure including cost of materials,labour charges,scaffolding,curing etc., complete as per superstructure	Sqm	447.89	1011.96	Rupees One Thousand Eleven And Paise Ninety Six Only
20	**Providing and constructing pre cast concrete solid blocks** with compressive strength not less than 35 kg/sqm with cement mortar 1:4 masonry (quoins, jamb,closer blocks) with solid concrete blocks of size 40x10x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials,labour charges,scaffolding,curing etc. complete as per superstructure	Sqm	20.10	875.88	Rupees Eight Hundred Seventy Five And Paise Eighty Eight Only
21	**Providing Honne wood frames of doors, windows**, clerestory windows, ventilators and other frames wrought, framed of assembled including making plaster grooves (excluding cost of materials, labour, HOM of machineries complete as per specifications	Cum	0.99	73228.32	Rupees Seventy Three Thousand Two Hundred Twenty Eight And Paise Thirty Two Only
	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm, thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour,HOM of machineries completed as per specification (excluding cost of fixtures)	Sqm	13.40	5099.76	Rupees Five Thousand Ninety Nine And Paise Seventy Six Only
	Providing and fixing in position shutters for loors made out of Honne wood styles and ails of 35mm. Thick with bottom and lock rail 80mm wide top rail and styles 100mm wide as er drawings and panels of 18mm thick is teriors grade melamine impregnated elaminations particle board colour on one es including cost of materials, labour, HOM machineries complete as per cifications.(excluding cost of fixtures)	Sqm	1.76	3722.76	Rupees Three Thousand Seven Hundred Twenty Two And Paise Seventy Six Only

	Providing and fixing M.S. grill work for windows and ventilator weighing 21kg/Sqm using M.S. flats, or M.S square rods or combination of M.S. flats and steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures labour and HOM of machinery specifications	Kg	1651.35	102.60	Rupees One Hundred Two And Paise Sixty Only
25	**Providing and fixing in position anodized alluminium windows and ventilators** as per approved drawings with sliding shutters using double track window frame section of size 122.2x31.75mm with 1.2mm thick, bottom section weight of 0.695 kg per m, sides and top section of 1.3mm thick weight of 0.659 kg per m and shutter comprising top and bottom section of size 40mmx18mm , 1.25mm thick of 0.417 kg per m shutter outer side 40mmx18mm, 1.25mm thick weight of 0.417 kg per m, shutter interlock section 40mmx 26.7mm , 1.1mm thick, wieght of 0.469 kg per m the shutter mounted on nylon roller with approved quality of fixture such as alluminium tower bolts etc., and providing and fixing 5.5mm thick plain glass of shutter fitted with rubber beading alluminium section anodized 12 to 15 microns including cutting to required length, joints mitred sub dividing the frame tenonned revited in the assembled frame stiffened with end clips at corners angles etc., and fixed to walls, lintles, floor beams or cills	Sqm	2.70	4020.84	Rupees Four Thousand Twenty And Paise Eighty Four Only
	Providing and fixing in position collapsible steel shutters with single or double leaf with vertical channel 20mmX10mmX2mm braced with flat iron diagonals 20mmx5mm size with top and bottom rails of T Iron sections of 40X40X6mm with 38mm dia steel pulleys complete with bolts and nuts, locking arrangements, stoppers, handles coat of red lead paint, cost of materials, labour, HOM of machinery complete as per specifications size of gate 2.4mX1.4m	Sqm	8.10	5626.80	Rupees Five Thousand Six Hundred Twenty Six And Paise Eighty Only

oviding 12mm thick cement plaster in ngle coat with cement mortar 1:3, to ing incluidng rounding off corners wherever required smooth rendering providing and removing scaffolding including cost of materials, labour curing complete as per specification	Sqm	474.78	253.80	Rupees Two Hundred Fifty Three And Pais Eighty Only
Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering: providing and removing scaffolding, including cost of materials labour curing complete as per specifications	Sqm	782.33	298.08	Rupees Two Hundred Nine Eight And Pais Eight Only
Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications	Sqm	1257.11	34.56	Rupees Thirty F And Paise Fifty Only
Providing 20mm thick cement plaster in ingle coat with cement mortar 1:3, to stone asonry & concrete surface including ounding off corners wherever required smooth ndering,: Providing and removing affolding, including cost of materials, labour, ring complete as per specifications	Sqm	473.79	319.68	Rupees Three Hundred Ninete And Paise Six Eight Only
SRB 15.8.1 Providing and fixing plaster sh 100mm wide manufactured out of hot ped galvanised iron of nominal thickness 5mm with a zinc coating of 120gms per sqm lth, along route of walls chipped for vices, junction between RCC and brick ls including cost of materials, labour for ng complete as per specifications, (length of h only be measured for payment) KSRB .2- d o -plaster mesh 150mm wide	Rmt	250.00	38.88	Rupees Thirt Eight And Pai Eighty Eight O

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON

104	Supply of 2'x2' LED recessed luminaire with ...Watts system wattage. Housing shall be with pressure die cast aluminum alloy with corrosion proof resistant polyester power coated. Driver operates with voltage range from 100V to 270V 50/60 Hz with short circuit, overload & mis-wiring protection. Lumen Maintenance of 70% at 50000 Hrs. Injection moulded poly carbonate diffuser for better mechanical stability, light transmission & avoid pot hole effect. Junction temperature shall be < 70 degree Celsius. Driver is on constant current driver @ 0.06A with PF > 0.92 with line voltage @ 220-240V @ 50/60Hz, driver efficiency > 85% & THD<15%. LED Efficiency > 130 lm/W at 1W & Fixture Efficiency >75lm/w with CRI > 75 with injection moulded Polycarbonate lens with < 80mm depth. 5 years Warranty against any manufacturing defect working under standard electrical condition LED modular down light 2'x2'-55 watts	Nos	6.00	9373.00	Rupees Nine Thousand Three Hundred Seventy Three Only
105	Supply of LED Square Recessed Down lighter with 18W System Wattage. Housing shall be with powder coated pressure die cast aluminum alloy with corrosion resistant polyester powder coat & with extended heat sink. Diffuser/cover made of Lexan plastic material. Rated life shall be L70 @ 50000 Hrs. which shall has inbuilt electrical protection like over/under voltage, short circuit, overload, open circuit & miswiring. Driver is on constant current driver output driver @ 0.06A with PF > 0.9 with line voltage @ 220-240V @ 50/60Hz, driver efficiency > 85% & THD<15%. LED Efficiency > 130 lm/W at 1W & Fixture Efficiency >75lm/w with CRI > 75 with injection moulded Polycarbonate lens. 5 years Warranty against any manufacturing defect working under standard electrical condition.	No	18.00	4945.00	Rupees Four Thousand Nine Hundred Forty Five Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73

106	LED Indoor Supplying of 2' feet - LED PVC Square Batten ..W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V @ 50Hz & Power factor >0.9 along with CE approved drivers. 5 years Warranty against any manufacturing defect working under standard electrical condition LED light fighting 4' - 28 watts	Nos	4.00	1774.00	Rupees One Thousand Seven Hundred Seventy Four Only
107	LED Post Top Lantern GARDEN.Supply of LED Post Top Lantern with system ... wattage, housing & frame shall be of powder coated, die cast aluminum, diffuser with high density polyethylene IP65 EPDM Gasket. Life 50000 Hrs. @ L70 shall be conforming to IS 10322/Part 5/ Section 5 @ 230V. 5 years Warranty against any manufacturing defect working under standard electrical condition LED Post Top Lantern with 24 watts	Nos	4.00	15930.00	Rupees Fifteen Thousand Nine Hundred Thirty Only
108	LED Down light Supply of recess mounted rolling type LED Down light with 4/6W GU 10 LED Lamp Rib Fabricated from Die cast aluminum with white powder coated prewired to mains connector with suitable driver & having swiveling unit of aluminum die cast eye ball & LED Lamp position retained by circular wire spring. 5 years Warranty against any manufacturing defect working under standard electrical condition. LED square or round down light 5x1 watts	Nos	10.00	1428.00	Rupees One Thousand Four Hundred Twenty Eight Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

109	Supplying of LED Floodlight with .....W System Power consumption pressure die cast aluminum housing with powder coating with IP 65 protection. 1, 200-275V voltage with electronic Driver, PF>0.9, should meet ANSI 2G Vibration test, Compliance to UL/CE with Class I. System rating shall be 50K hrs. @ Lumen maintenance of 70%, system efficacy > 80lm/w. Over load & Short circuit protection ensures reliable operation in spite of problem in output side. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. LED Light fixture with .....W System Power consumption. LED Efficiency>130lm/w at 1W & Fixture Efficiency >80lm/w with nominal CRI >75. Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008 Housing with supplier word mark	Nos	4.00	14646.00	Rupees Fourteen Thousand Six Hundred Forty Six Only
110	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A. 3.5 core 25 sqmm	Mtrs	120.00	165.60	Rupees One Hundred Sixty Fiv And Paise Sixty Only
111	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct. 25 sqmm to 75 sqmm	Mtrs	120.00	16.20	Rupees Sixteen And Paise Twen Only
112	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7)In soil (ordinary)	Mtrs	70.00	78.00	Rupees Seventy Eight Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palik
Dasarahalli Division, Bengaluru-73

113	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit … The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia	Nos	3.00	2727.00	Rupees Two Thousand Seven Hundred Twenty Seven Only
114	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required. GI strip	Mtrs	100.00	77.00	Rupees Seventy Seven Only
115	Fabricating supplying and mounting MS box made out … SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc. complete 16SWG	Sq CM	13200.00	0.33	Rupees And Paise Thirty Three Only
116	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.40-63 Amps SP	Nos	10.00	677.00	Rupees Six Hundred Seventy Seven Only
117	5-32 Amps DP	Nos	4.00	849.00	Rupees Eight Hundred Forty Nine Only
118	.40-63Amps TPN	Nos	1.00	1963.00	Rupees One Thousand Nine Hundred Sixty Three Only
19	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers.100Amps	Nos	3.00	360.00	Rupees Three Hundred Sixty Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Begurahalli Division, Bengaluru-73.

120	Fabricating, supplying and erection of …Mtrs long hot dip Galvanized Conical pole with BSEN 10025 grade S 355 JO steel plate for shaft, IS 2062 for base plate with door opening arrangements, including suitable boards, Bakelite sheet and MCBs as per IS specifications suitable to withstand the wind speed of 47 m/sec for …….Mtrs pole in single section and single joint welded as per IS 9595/IS 10178AWS having dimensions bottom …..mm, top….mm with 3mm thick, suitable base plate and 4Nos of ..... long J bolts along with template and the pole shall be hot dip galvanized in single dipping with not less than 65micron as per ASTM-A123 and 153 etc.,(excluding foundation) as per drawing appended.7 meters - Top 75mm and bottom	Nos	2.00	14040.00	Rupees Fourteen Thousand Forty Only
121	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV.40mm	Mtrs	5.00	345.00	Rupees Three Hundred Forty Five Only
122	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc.25Sqmm	Nos	1.00	362.00	Rupees Three Hundred Sixty Two Only
3	Supplying and fixing hylum plastic sheet 3mm thick with necessary nitches for fixing switches, regulators etc., and fixing on existing wood or metal box using N.F. screws.	Sq CM	3600.00	0.22	Rupees And Paise Twenty Two Only
	Providing Rcc Pole pedstal of Size 0.5x0.5x1.6 Mtrs Including digging of pit, tor steel, anchoring bolts nuts ,templates ,Centring,1;4;8base concrete,1;2;4pedestal concrete and etc coplete as per the data sheet enclosed	Nos	2.00	4199.00	Rupees Four Thousand One Hundred Ninety Nine Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

125	Supplying of…TR split Air conditioners suitable for operation on A/C supply single phase 50 Hz 230 Volts with hermetically sealed compressor with air cooled condenser, motor capacitor and start run capacitors, relay and over load protector internal unit, with one indoor and one outdoor unit. The condenser unit will be placed outside the room on the terrace to avoid noise including standard length of suitable size copper tubing covered with insulation tube.(High wall chorded/cordless) suitable capacity 3 core sheathed/ PVC copper cable and a battery operated wireless remote unit. 5star 2 ton capacity	Nos	2.00	67060.00	Rupees Sixty Seven Thousand Sixty Only
126	Supplying and installation of insulated refrigerant copper tubing of 5/8`` and 3/8`` with polythene foam insulation 3 core 80 stand copper wiring between indoor and outdoor unit. Leak testing oil and gas charging for additional piping length of tube.Split	Mtrs	20.00	1193.00	Rupees One Thousand One Hundred Ninety Three Only
127	Supplying, erecting, testing and commissioning of voltage stabilizer suitable for 170 to 270 v in put and load variation from no load to full load, with over load protection, spike suppression, operating at 00 C to 400 C. Range etc., complete.4KVA Capacity	Nos	2.00	4317.00	Rupees Four Thousand Three Hundred Seventee Only
128	Bescom Charge	L/S		7348.00	Rupees Seven Thousand Thre Hundred Forty Eight Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.